


'Crafts'_Elevation H

Existing deep red MDF wall to be redecorated in grey emulsion paint (colour TBC)

875mm high x 12mm thick MDF panel with DTM graphic print to front face mounted to wall via aluminium split battens

Existing 'Desk Case'

New 'Desk Case' mounted to worktop




'Crafts'_ Plan

Front edge of worktop in welded 50x50 SHS. Powdercoat finish (colour TBC)

Existing 'Desk Case' free-issue from M-shed. MDF carcass to be decorated in conservation-grade paint finish to interior. Exterior in 2 pack cellulose lacquer to match worktop

New 340mm high x 600 x 600mm 'Desk Case' to replicate M-Shed cases. 12mm ZF-MDF carcass to be decorated in conservation-grade paint finish to interior. Exterior in 2 pack cellulose lacquer to match worktop. 5mm clear acrylic top with external graphic strip along front edge



Sketch Visual

Existing deep red MDF wall to be redecorated in grey emulsion paint (colour TBC)

875mm high x 12mm thick MDF panel with DTM graphic print to front face

Existing 'Desk Case'

New 'Desk Case' mounted to worktop

<div>General Notes:</div> <div>01. Do not scale. 02. Verify all dimensions before commencing work. 03. Report all discrepancies or omissions. 04. All dimensions in millimetres unless stated otherwise.</div>	<div>Status:</div> <div>TENDER</div>	Revisions:			Revisions:			<div>Project</div> <div>A HISTORY OF PLACE</div> <div>M-SHED BRISTOL</div>	<div>Title</div> <div>'CRAFT' DETAILS</div>	<div>Job No.</div> <div>148</div>	<div>Scale</div> <div>1:20@A3</div>	<div>Date</div> <div>16.07.17</div>	<div>Project East Design</div> <div>1 York Road</div> <div>London E7 9HT</div> <div>Tel: 020 8503 0277</div> <div>Mob: 07967 507660</div>
		<div>Rev</div>	<div>Date</div>	<div>Description</div>	<div>Rev</div>	<div>Date</div>	<div>Description</div>			<div>Drawing No.</div> <div>148_211</div>	<div>Rev</div> <div>/</div>		